




United States
Department of
Agriculture

NRCS

Natural
Resources
Conservation
Service

A product of the National
Cooperative Soil Survey,
a joint effort of the United
States Department of
Agriculture and other
Federal agencies, State
agencies including the
Agricultural Experiment
Stations, and local
participants

Custom Soil Resource Report for Hill County, Texas, Limestone County, Texas, and McLennan County, Texas



Preface

Soil surveys contain information that affects land use planning in survey areas. They highlight soil limitations that affect various land uses and provide information about the properties of the soils in the survey areas. Soil surveys are designed for many different users, including farmers, ranchers, foresters, agronomists, urban planners, community officials, engineers, developers, builders, and home buyers. Also, conservationists, teachers, students, and specialists in recreation, waste disposal, and pollution control can use the surveys to help them understand, protect, or enhance the environment.

Various land use regulations of Federal, State, and local governments may impose special restrictions on land use or land treatment. Soil surveys identify soil properties that are used in making various land use or land treatment decisions. The information is intended to help the land users identify and reduce the effects of soil limitations on various land uses. The landowner or user is responsible for identifying and complying with existing laws and regulations.

Although soil survey information can be used for general farm, local, and wider area planning, onsite investigation is needed to supplement this information in some cases. Examples include soil quality assessments (<http://www.nrcs.usda.gov/wps/portal/nrcs/main/soils/health/>) and certain conservation and engineering applications. For more detailed information, contact your local USDA Service Center (<https://offices.sc.egov.usda.gov/locator/app?agency=nrcs>) or your NRCS State Soil Scientist (http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/contactus/?cid=nrcs142p2_053951).

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

The National Cooperative Soil Survey is a joint effort of the United States Department of Agriculture and other Federal agencies, State agencies including the Agricultural Experiment Stations, and local agencies. The Natural Resources Conservation Service (NRCS) has leadership for the Federal part of the National Cooperative Soil Survey.

Information about soils is updated periodically. Updated information is available through the NRCS Web Soil Survey, the site for official soil survey information.

The U.S. Department of Agriculture (USDA) prohibits discrimination in all its programs and activities on the basis of race, color, national origin, age, disability, and where applicable, sex, marital status, familial status, parental status, religion, sexual orientation, genetic information, political beliefs, reprisal, or because all or a part of an individual's income is derived from any public assistance program. (Not all prohibited bases apply to all programs.) Persons with disabilities who require

alternative means for communication of program information (Braille, large print, audiotape, etc.) should contact USDA's TARGET Center at (202) 720-2600 (voice and TDD). To file a complaint of discrimination, write to USDA, Director, Office of Civil Rights, 1400 Independence Avenue, S.W., Washington, D.C. 20250-9410 or call (800) 795-3272 (voice) or (202) 720-6382 (TDD). USDA is an equal opportunity provider and employer.

Contents

Preface	2
How Soil Surveys Are Made	5
Soil Map	8
Soil Map.....	9
Legend.....	10
Map Unit Legend.....	12
Map Unit Descriptions.....	13
Hill County, Texas.....	15
39—Ferris-Heiden complex, 2 to 5 percent slopes.....	15
74—Tinn clay, 0 to 1 percent slopes, frequently flooded.....	17
80—Wilson clay loam, 1 to 3 percent slopes.....	18
Limestone County, Texas.....	21
AxB—Axtell fine sandy loam, 1 to 3 percent slopes.....	21
CrB—Crockett loam, 1 to 3 percent slopes.....	22
FeD2—Ferris clay, 5 to 15 percent slopes, eroded.....	23
FhC2—Ferris-Heiden complex, 2 to 5 percent slopes, eroded.....	25
HeB—Heiden clay, 1 to 3 percent slopes.....	27
To—Tinn clay, 0 to 1 percent slopes, frequently flooded.....	29
W—Water.....	30
Wf—Whitesboro loam, frequently flooded.....	30
WnA—Wilson clay loam, 0 to 2 percent slopes.....	31
McLennan County, Texas.....	34
CrB—Crockett loam, 3 to 5 percent slopes.....	34
HeC—Heiden clay, 3 to 5 percent slopes.....	35
WnA—Wilson clay loam, 0 to 2 percent slopes.....	37
References	39

How Soil Surveys Are Made

Soil surveys are made to provide information about the soils and miscellaneous areas in a specific area. They include a description of the soils and miscellaneous areas and their location on the landscape and tables that show soil properties and limitations affecting various uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants; and the kinds of bedrock. They observed and described many soil profiles. A soil profile is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed or from the surface down to bedrock. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

Currently, soils are mapped according to the boundaries of major land resource areas (MLRAs). MLRAs are geographically associated land resource units that share common characteristics related to physiography, geology, climate, water resources, soils, biological resources, and land uses (USDA, 2006). Soil survey areas typically consist of parts of one or more MLRA.

The soils and miscellaneous areas in a survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landform or with a segment of the landform. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landform, a soil scientist develops a concept, or model, of how they were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted soil color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. Soil taxonomy, the system of taxonomic classification used in the United States, is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil

Custom Soil Resource Report

scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

The objective of soil mapping is not to delineate pure map unit components; the objective is to separate the landscape into landforms or landform segments that have similar use and management requirements. Each map unit is defined by a unique combination of soil components and/or miscellaneous areas in predictable proportions. Some components may be highly contrasting to the other components of the map unit. The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The delineation of such landforms and landform segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, onsite investigation is needed to define and locate the soils and miscellaneous areas.

Soil scientists make many field observations in the process of producing a soil map. The frequency of observation is dependent upon several factors, including scale of mapping, intensity of mapping, design of map units, complexity of the landscape, and experience of the soil scientist. Observations are made to test and refine the soil-landscape model and predictions and to verify the classification of the soils at specific locations. Once the soil-landscape model is refined, a significantly smaller number of measurements of individual soil properties are made and recorded. These measurements may include field measurements, such as those for color, depth to bedrock, and texture, and laboratory measurements, such as those for content of sand, silt, clay, salt, and other components. Properties of each soil typically vary from one point to another across the landscape.

Observations for map unit components are aggregated to develop ranges of characteristics for the components. The aggregated values are presented. Direct measurements do not exist for every property presented for every map unit component. Values for some properties are estimated from combinations of other properties.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists. For example, data on crop yields under defined levels of management are assembled from farm records and from field or plot experiments on the same kinds of soil.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot predict that a high water table will always be at a specific level in the soil on a specific date.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and


Custom Soil Resource Report

identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.


Soil Map

The soil map section includes the soil map for the defined area of interest, a list of soil map units on the map and extent of each map unit, and cartographic symbols displayed on the map. Also presented are various metadata about data used to produce the map, and a description of each soil map unit.

Custom Soil Resource Report Soil Map



Map Scale: 1:13,800 if printed on A portrait (8.5" x 11") sheet.



Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 14N WGS84

MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

 Soil Map Unit Polygons

 Soil Map Unit Lines

 Soil Map Unit Points

Special Point Features

-  Blowout
-  Borrow Pit
-  Clay Spot
-  Closed Depression
-  Gravel Pit
-  Gravelly Spot
-  Landfill
-  Lava Flow
-  Marsh or swamp
-  Mine or Quarry
-  Miscellaneous Water
-  Perennial Water
-  Rock Outcrop
-  Saline Spot
-  Sandy Spot
-  Severely Eroded Spot
-  Sinkhole
-  Slide or Slip
-  Sodic Spot

-  Spoil Area
-  Stony Spot
-  Very Stony Spot
-  Wet Spot
-  Other
-  Special Line Features

Water Features

 Streams and Canals

Transportation

-  Rails
-  Interstate Highways
-  US Routes
-  Major Roads
-  Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at scales ranging from 1:20,000 to 1:24,000.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Hill County, Texas
 Survey Area Data: Version 12, Sep 15, 2016

Soil Survey Area: Limestone County, Texas
 Survey Area Data: Version 12, Sep 16, 2016

Soil Survey Area: McLennan County, Texas
 Survey Area Data: Version 14, Sep 19, 2016

Your area of interest (AOI) includes more than one soil survey area. These survey areas may have been mapped at different scales, with a different land use in mind, at different times, or at different levels of detail. This may result in map unit symbols, soil properties, and interpretations that do not completely agree across soil survey area boundaries.

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 8, 2013—Mar 19, 2017

MAP LEGEND

MAP INFORMATION

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Map Unit Legend

Hill County, Texas (TX217)			
Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
39	Ferris-Heiden complex, 2 to 5 percent slopes	0.0	0.0%
74	Tinn clay, 0 to 1 percent slopes, frequently flooded	0.1	0.0%
80	Wilson clay loam, 1 to 3 percent slopes	0.0	0.0%
Subtotals for Soil Survey Area		0.2	0.0%
Totals for Area of Interest		499.2	100.0%

Limestone County, Texas (TX293)			
Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
AxB	Axtell fine sandy loam, 1 to 3 percent slopes	159.9	32.0%
CrB	Crockett loam, 1 to 3 percent slopes	4.5	0.9%
FeD2	Ferris clay, 5 to 15 percent slopes, eroded	32.4	6.5%
FhC2	Ferris-Heiden complex, 2 to 5 percent slopes, eroded	18.5	3.7%
HeB	Heiden clay, 1 to 3 percent slopes	38.5	7.7%
To	Tinn clay, 0 to 1 percent slopes, frequently flooded	57.9	11.6%
W	Water	3.8	0.8%
Wf	Whitesboro loam, frequently flooded	0.0	0.0%
WnA	Wilson clay loam, 0 to 2 percent slopes	109.6	22.0%
Subtotals for Soil Survey Area		425.1	85.2%
Totals for Area of Interest		499.2	100.0%

McLennan County, Texas (TX309)			
Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
CrB	Crockett loam, 3 to 5 percent slopes	12.6	2.5%
HeC	Heiden clay, 3 to 5 percent slopes	18.5	3.7%
WnA	Wilson clay loam, 0 to 2 percent slopes	42.9	8.6%
Subtotals for Soil Survey Area		73.9	14.8%
Totals for Area of Interest		499.2	100.0%

Map Unit Descriptions

The map units delineated on the detailed soil maps in a soil survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions, along with the maps, can be used to determine the composition and properties of a unit.

A map unit delineation on a soil map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some minor components that belong to taxonomic classes other than those of the major soils.

Most minor soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, components. They may or may not be mentioned in a particular map unit description. Other minor components, however, have properties and behavioral characteristics divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, components. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. If included in the database for a given area, the contrasting minor components are identified in the map unit descriptions along with some characteristics of each. A few areas of minor components may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of minor components in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into landforms or landform segments that have similar use and management requirements. The delineation of such segments on the map provides sufficient information for the development of resource plans. If intensive use of small areas is planned, however, onsite investigation is needed to define and locate the soils and miscellaneous areas.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives important soil properties and qualities.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the surface layer, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the surface layer, slope, stoniness, salinity, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas

Custom Soil Resource Report

shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Alpha silt loam, 0 to 2 percent slopes, is a phase of the Alpha series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are complexes, associations, or undifferentiated groups.

A *complex* consists of two or more soils or miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Alpha-Beta complex, 0 to 6 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Alpha-Beta association, 0 to 2 percent slopes, is an example.

An *undifferentiated group* is made up of two or more soils or miscellaneous areas that could be mapped individually but are mapped as one unit because similar interpretations can be made for use and management. The pattern and proportion of the soils or miscellaneous areas in a mapped area are not uniform. An area can be made up of only one of the major soils or miscellaneous areas, or it can be made up of all of them. Alpha and Beta soils, 0 to 2 percent slopes, is an example.

Some surveys include *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rock outcrop is an example.

Hill County, Texas

39—Ferris-Heiden complex, 2 to 5 percent slopes

Map Unit Setting

National map unit symbol: 2v1v7
Elevation: 320 to 920 feet
Mean annual precipitation: 35 to 39 inches
Mean annual air temperature: 64 to 66 degrees F
Frost-free period: 233 to 257 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Ferris and similar soils: 50 percent
Heiden and similar soils: 40 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Ferris

Setting

Landform: Ridges
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Microfeatures of landform position: Linear gilgai
Down-slope shape: Linear
Across-slope shape: Convex
Parent material: Clayey residuum weathered from mudstone

Typical profile

Ap - 0 to 10 inches: clay
Bkss1 - 10 to 30 inches: clay
Bkss2 - 30 to 45 inches: clay
Cdk - 45 to 60 inches: clay

Properties and qualities

Slope: 3 to 5 percent
Depth to restrictive feature: 39 to 60 inches to densic bedrock
Natural drainage class: Well drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 30 percent
Gypsum, maximum in profile: 5 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Sodium adsorption ratio, maximum in profile: 12.0
Available water storage in profile: Moderate (about 7.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e

Custom Soil Resource Report

Hydrologic Soil Group: D

Ecological site: Eroded Blackland 28-40" PZ (R086AY201TX)

Hydric soil rating: No

Description of Heiden

Setting

Landform: Ridges

Landform position (two-dimensional): Shoulder, backslope

Landform position (three-dimensional): Interfluvium, side slope

Microfeatures of landform position: Linear gilgai

Down-slope shape: Convex

Across-slope shape: Convex

Parent material: Clayey residuum weathered from mudstone

Typical profile

Ap - 0 to 5 inches: clay

A - 5 to 15 inches: clay

Bkss1 - 15 to 38 inches: clay

Bkss2 - 38 to 64 inches: clay

CBdk - 64 to 80 inches: clay

Properties and qualities

Slope: 2 to 4 percent

Depth to restrictive feature: 48 to 65 inches to densic material

Natural drainage class: Well drained

Runoff class: Very high

Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 40 percent

Gypsum, maximum in profile: 5 percent

Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Sodium adsorption ratio, maximum in profile: 12.0

Available water storage in profile: High (about 9.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: D

Ecological site: Blackland 28-40" PZ (R086AY196TX)

Hydric soil rating: No

Minor Components

Altoga

Percent of map unit: 5 percent

Landform: Stream terraces

Landform position (three-dimensional): Riser

Down-slope shape: Linear

Across-slope shape: Convex

Ecological site: Clay Loam 28-40" PZ (R086AY199TX)

Hydric soil rating: No

Ferris, moderately eroded

Percent of map unit: 5 percent
Landform: Ridges
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Microfeatures of landform position: Linear gilgai
Down-slope shape: Linear
Across-slope shape: Convex
Ecological site: Eroded Blackland 28-40" PZ (R086AY201TX)
Hydric soil rating: No

74—Tinn clay, 0 to 1 percent slopes, frequently flooded

Map Unit Setting

National map unit symbol: 2vtgr
Elevation: 330 to 750 feet
Mean annual precipitation: 35 to 47 inches
Mean annual air temperature: 63 to 68 degrees F
Frost-free period: 226 to 263 days
Farmland classification: Not prime farmland

Map Unit Composition

Tinn and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Tinn

Setting

Landform: Flood plains
Landform position (three-dimensional): Tread
Microfeatures of landform position: Circular gilgai
Down-slope shape: Linear
Across-slope shape: Concave
Parent material: Calcareous clayey alluvium

Typical profile

A - 0 to 17 inches: clay
Bss - 17 to 57 inches: clay
Bkssy - 57 to 80 inches: clay

Properties and qualities

Slope: 0 to 1 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Moderately well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)
Depth to water table: More than 80 inches

Custom Soil Resource Report

Frequency of flooding: Frequent
Frequency of ponding: None
Calcium carbonate, maximum in profile: 25 percent
Gypsum, maximum in profile: 2 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Sodium adsorption ratio, maximum in profile: 2.0
Available water storage in profile: Moderate (about 8.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 5w
Hydrologic Soil Group: D
Ecological site: Clayey Bottomland 28-40" PZ (R086AY198TX)
Hydric soil rating: No

Minor Components

Whitesboro

Percent of map unit: 10 percent
Landform: Flood plains
Microfeatures of landform position: Circular gilgai
Down-slope shape: Linear
Across-slope shape: Concave
Ecological site: Loamy Bottomland 28-40" PZ (R086AY203TX)
Hydric soil rating: No

Gladewater

Percent of map unit: 5 percent
Landform: Flood plains
Down-slope shape: Concave
Across-slope shape: Concave
Ecological site: Clayey Bottomland 28-40" PZ (R086AY198TX)
Hydric soil rating: Yes

80—Wilson clay loam, 1 to 3 percent slopes

Map Unit Setting

National map unit symbol: 2wg9f
Elevation: 200 to 770 feet
Mean annual precipitation: 34 to 48 inches
Mean annual air temperature: 64 to 67 degrees F
Frost-free period: 243 to 262 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Wilson and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Wilson

Setting

Landform: Stream terraces, stream terraces
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Concave
Parent material: Loamy and/or clayey alluvium derived from mudstone

Typical profile

Ap - 0 to 7 inches: clay loam
Btss - 7 to 31 inches: clay
Btkss - 31 to 36 inches: clay
Btkssyg - 36 to 42 inches: clay
Btkyg - 42 to 80 inches: clay loam

Properties and qualities

Slope: 1 to 3 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Moderately well drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 20 percent
Gypsum, maximum in profile: 15 percent
Salinity, maximum in profile: Very slightly saline to moderately saline (2.0 to 8.0 mmhos/cm)
Sodium adsorption ratio, maximum in profile: 10.0
Available water storage in profile: Moderate (about 7.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3w
Hydrologic Soil Group: D
Ecological site: Claypan Prairie 28-40" PZ (R086AY200TX)
Hydric soil rating: No

Minor Components

Burleson

Percent of map unit: 10 percent
Landform: Stream terraces, stream terraces
Landform position (three-dimensional): Tread
Microfeatures of landform position: Circular gilgai, circular gilgai
Down-slope shape: Linear
Across-slope shape: Linear
Ecological site: Blackland 28-40" PZ (R086AY196TX)
Hydric soil rating: No

Crockett

Percent of map unit: 5 percent
Landform: Ridges, stream terraces
Landform position (two-dimensional): Summit, shoulder

Custom Soil Resource Report

Landform position (three-dimensional): Interfluve, tread

Down-slope shape: Linear

Across-slope shape: Convex

Ecological site: Claypan Prairie 28-40" PZ (R086AY200TX)

Hydric soil rating: No

Limestone County, Texas

AxB—Axtell fine sandy loam, 1 to 3 percent slopes

Map Unit Setting

National map unit symbol: 2shg6

Elevation: 200 to 790 feet

Mean annual precipitation: 33 to 47 inches

Mean annual air temperature: 65 to 67 degrees F

Frost-free period: 240 to 270 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Axtell and similar soils: 87 percent

Minor components: 13 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Axtell

Setting

Landform: Stream terraces, stream terraces, stream terraces

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Linear, convex

Parent material: Clayey alluvium of pleistocene age derived from mudstone

Typical profile

A - 0 to 10 inches: fine sandy loam

Btss - 10 to 18 inches: clay

Btk1 - 18 to 46 inches: clay

Btk2 - 46 to 80 inches: clay

Properties and qualities

Slope: 1 to 3 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Moderately well drained

Runoff class: Medium

Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 15 percent

Gypsum, maximum in profile: 5 percent

Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Sodium adsorption ratio, maximum in profile: 5.0

Available water storage in profile: Moderate (about 7.0 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: D

Ecological site: Claypan Savannah 28-40 PZ (R087AY221TX)

Hydric soil rating: No

Minor Components

Mabank

Percent of map unit: 7 percent
Landform: Stream terraces, stream terraces
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Concave
Ecological site: Claypan Prairie 28-40" PZ (R086AY200TX)
Hydric soil rating: No

Rader

Percent of map unit: 6 percent
Landform: Stream terraces, stream terraces, stream terraces
Landform position (three-dimensional): Tread
Down-slope shape: Linear
Across-slope shape: Convex, concave, linear
Ecological site: Sandy Loam 28-40" PZ (R087AY237TX)
Hydric soil rating: No

CrB—Crockett loam, 1 to 3 percent slopes

Map Unit Setting

National map unit symbol: 2ssh6
Elevation: 280 to 860 feet
Mean annual precipitation: 34 to 43 inches
Mean annual air temperature: 63 to 67 degrees F
Frost-free period: 234 to 271 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Crockett and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Crockett

Setting

Landform: Ridges
Landform position (two-dimensional): Shoulder, summit
Landform position (three-dimensional): Interfluve
Down-slope shape: Linear
Across-slope shape: Convex
Parent material: Loamy residuum weathered from shale of cretaceous age

Typical profile

A - 0 to 8 inches: loam
Btss - 8 to 25 inches: clay
Btkss - 25 to 45 inches: clay
BCK - 45 to 53 inches: clay

Custom Soil Resource Report

Cdk - 53 to 72 inches: clay loam

Properties and qualities

Slope: 1 to 3 percent

Depth to restrictive feature: 43 to 60 inches to densic bedrock

Natural drainage class: Moderately well drained

Runoff class: Very high

Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.03 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 30 percent

Gypsum, maximum in profile: 2 percent

Salinity, maximum in profile: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)

Sodium adsorption ratio, maximum in profile: 10.0

Available water storage in profile: Moderate (about 8.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3e

Hydrologic Soil Group: D

Ecological site: Claypan Prairie 28-40" PZ (R086AY200TX)

Hydric soil rating: No

Minor Components

Normangee

Percent of map unit: 10 percent

Landform: Ridges

Landform position (two-dimensional): Shoulder, summit

Landform position (three-dimensional): Interfluvium

Down-slope shape: Linear

Across-slope shape: Convex

Ecological site: Claypan Prairie 28-40" PZ (R086AY200TX)

Hydric soil rating: No

Wilson

Percent of map unit: 5 percent

Landform: Stream terraces

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Concave

Ecological site: Claypan Prairie 28-40" PZ (R086AY200TX)

Hydric soil rating: No

FeD2—Ferris clay, 5 to 15 percent slopes, eroded

Map Unit Setting

National map unit symbol: ddcz

Elevation: 400 to 1,000 feet

Custom Soil Resource Report

Mean annual precipitation: 28 to 42 inches
Mean annual air temperature: 64 to 70 degrees F
Frost-free period: 230 to 260 days
Farmland classification: Not prime farmland

Map Unit Composition

Ferris, eroded, and similar soils: 100 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Ferris, Eroded

Setting

Landform: Ridges
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Microfeatures of landform position: Linear gilgai
Down-slope shape: Linear
Across-slope shape: Convex
Parent material: Residuum weathered from calcareous shale in eagleford shale and taylor marl formations of cretaceous age

Typical profile

H1 - 0 to 4 inches: clay
H2 - 4 to 45 inches: clay
H3 - 45 to 80 inches: clay

Properties and qualities

Slope: 5 to 15 percent
Depth to restrictive feature: 40 to 60 inches to densic bedrock
Natural drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 30 percent
Gypsum, maximum in profile: 5 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Sodium adsorption ratio, maximum in profile: 5.0
Available water storage in profile: Moderate (about 6.8 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 6e
Hydrologic Soil Group: D
Ecological site: Eroded Blackland 28-40" PZ (R086AY201TX)
Hydric soil rating: No

FhC2—Ferris-Heiden complex, 2 to 5 percent slopes, eroded

Map Unit Setting

National map unit symbol: 2sshj
Elevation: 400 to 720 feet
Mean annual precipitation: 42 to 44 inches
Mean annual air temperature: 63 to 66 degrees F
Frost-free period: 232 to 254 days
Farmland classification: Not prime farmland

Map Unit Composition

Ferris, eroded, and similar soils: 50 percent
Heiden, eroded, and similar soils: 40 percent
Minor components: 10 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Ferris, Eroded

Setting

Landform: Ridges
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Microfeatures of landform position: Linear gilgai
Down-slope shape: Linear
Across-slope shape: Convex
Parent material: Clayey residuum weathered from mudstone

Typical profile

Ap - 0 to 10 inches: clay
Bkss1 - 10 to 30 inches: clay
Bkss2 - 30 to 45 inches: clay
Cdk - 45 to 60 inches: clay

Properties and qualities

Slope: 3 to 5 percent
Depth to restrictive feature: 39 to 60 inches to densic bedrock
Natural drainage class: Well drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 30 percent
Gypsum, maximum in profile: 5 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Sodium adsorption ratio, maximum in profile: 12.0
Available water storage in profile: Moderate (about 7.6 inches)

Custom Soil Resource Report

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: D
Ecological site: Eroded Blackland 28-40" PZ (R086AY201TX)
Hydric soil rating: No

Description of Heiden, Eroded

Setting

Landform: Ridges
Landform position (two-dimensional): Backslope, shoulder
Landform position (three-dimensional): Interfluve, side slope
Microfeatures of landform position: Linear gilgai
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Clayey residuum weathered from mudstone

Typical profile

Ap - 0 to 5 inches: clay
A - 5 to 15 inches: clay
Bkss1 - 15 to 38 inches: clay
Bkss2 - 38 to 64 inches: clay
CBdk - 64 to 80 inches: clay

Properties and qualities

Slope: 2 to 4 percent
Depth to restrictive feature: 48 to 65 inches to densic material
Natural drainage class: Well drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 40 percent
Gypsum, maximum in profile: 5 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Sodium adsorption ratio, maximum in profile: 12.0
Available water storage in profile: High (about 9.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: D
Ecological site: Eroded Blackland 28-40" PZ (R086AY201TX)
Hydric soil rating: No

Minor Components

Ferris, moderately eroded

Percent of map unit: 5 percent
Landform: Ridges
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope

Custom Soil Resource Report

Microfeatures of landform position: Linear gilgai
Down-slope shape: Linear
Across-slope shape: Convex
Ecological site: Eroded Blackland 28-40" PZ (R086AY201TX)
Hydric soil rating: No

Houston black

Percent of map unit: 5 percent
Landform: Ridges
Landform position (two-dimensional): Shoulder
Landform position (three-dimensional): Interfluve
Microfeatures of landform position: Linear gilgai
Down-slope shape: Convex
Across-slope shape: Convex
Ecological site: Blackland 28-40" PZ (R086AY196TX)
Hydric soil rating: No

HeB—Heiden clay, 1 to 3 percent slopes

Map Unit Setting

National map unit symbol: 2v1v9
Elevation: 290 to 1,020 feet
Mean annual precipitation: 33 to 45 inches
Mean annual air temperature: 63 to 68 degrees F
Frost-free period: 224 to 278 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Heiden and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Heiden

Setting

Landform: Ridges
Landform position (two-dimensional): Summit, shoulder
Landform position (three-dimensional): Interfluve
Microfeatures of landform position: Linear gilgai
Down-slope shape: Convex
Across-slope shape: Linear
Parent material: Clayey residuum weathered from mudstone

Typical profile

Ap - 0 to 6 inches: clay
A - 6 to 18 inches: clay
Bkss - 18 to 58 inches: clay
CBdk - 58 to 70 inches: clay

Custom Soil Resource Report

Properties and qualities

Slope: 1 to 3 percent
Depth to restrictive feature: 40 to 65 inches to densic material
Natural drainage class: Well drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 40 percent
Gypsum, maximum in profile: 5 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Sodium adsorption ratio, maximum in profile: 12.0
Available water storage in profile: High (about 9.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 2e
Hydrologic Soil Group: D
Ecological site: Blackland 28-40" PZ (R086AY196TX)
Hydric soil rating: No

Minor Components

Houston black

Percent of map unit: 10 percent
Landform: Ridges
Landform position (two-dimensional): Shoulder, summit
Landform position (three-dimensional): Interfluvium
Microfeatures of landform position: Circular gilgai
Down-slope shape: Convex
Across-slope shape: Linear
Ecological site: Blackland 28-40" PZ (R086AY196TX)
Hydric soil rating: No

Ferris

Percent of map unit: 5 percent
Landform: Ridges
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Microfeatures of landform position: Linear gilgai
Down-slope shape: Linear
Across-slope shape: Convex
Ecological site: Eroded Blackland 28-40" PZ (R086AY201TX)
Hydric soil rating: No

To—Tinn clay, 0 to 1 percent slopes, frequently flooded

Map Unit Setting

National map unit symbol: 2vtgr
Elevation: 330 to 750 feet
Mean annual precipitation: 35 to 47 inches
Mean annual air temperature: 63 to 68 degrees F
Frost-free period: 226 to 263 days
Farmland classification: Not prime farmland

Map Unit Composition

Tinn and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Tinn

Setting

Landform: Flood plains
Landform position (three-dimensional): Tread
Microfeatures of landform position: Circular gilgai
Down-slope shape: Linear
Across-slope shape: Concave
Parent material: Calcareous clayey alluvium

Typical profile

A - 0 to 17 inches: clay
Bss - 17 to 57 inches: clay
Bkssy - 57 to 80 inches: clay

Properties and qualities

Slope: 0 to 1 percent
Depth to restrictive feature: More than 80 inches
Natural drainage class: Moderately well drained
Runoff class: High
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: Frequent
Frequency of ponding: None
Calcium carbonate, maximum in profile: 25 percent
Gypsum, maximum in profile: 2 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Sodium adsorption ratio, maximum in profile: 2.0
Available water storage in profile: Moderate (about 8.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 5w

Custom Soil Resource Report

Hydrologic Soil Group: D

Ecological site: Clayey Bottomland 28-40" PZ (R086AY198TX)

Hydric soil rating: No

Minor Components

Whitesboro

Percent of map unit: 10 percent

Landform: Flood plains

Microfeatures of landform position: Circular gilgai

Down-slope shape: Linear

Across-slope shape: Concave

Ecological site: Loamy Bottomland 28-40" PZ (R086AY203TX)

Hydric soil rating: No

Gladewater

Percent of map unit: 5 percent

Landform: Flood plains

Down-slope shape: Concave

Across-slope shape: Concave

Ecological site: Clayey Bottomland 28-40" PZ (R086AY198TX)

Hydric soil rating: Yes

W—Water

Map Unit Composition

Water: 100 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Wf—Whitesboro loam, frequently flooded

Map Unit Setting

National map unit symbol: ddf9

Elevation: 170 to 570 feet

Mean annual precipitation: 34 to 40 inches

Mean annual air temperature: 63 to 70 degrees F

Frost-free period: 225 to 275 days

Farmland classification: Not prime farmland

Map Unit Composition

Whitesboro and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Whitesboro

Setting

Landform: Flood plains

Down-slope shape: Linear

Custom Soil Resource Report

Across-slope shape: Concave

Parent material: Loamy alluvium of holocene age derived from mixed sources

Typical profile

H1 - 0 to 26 inches: loam

H2 - 26 to 58 inches: clay loam

H3 - 58 to 80 inches: sandy clay loam

Properties and qualities

Slope: 0 to 1 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Moderately well drained

Capacity of the most limiting layer to transmit water (Ksat): Moderately high to high (0.57 to 1.98 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: Frequent

Frequency of ponding: None

Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)

Available water storage in profile: High (about 9.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 5w

Hydrologic Soil Group: B

Ecological site: Loamy Bottomland 28-40" PZ (R086AY203TX)

Hydric soil rating: No

Minor Components

Unnamed, hydric

Percent of map unit: 8 percent

Landform: Depressions

Hydric soil rating: Yes

Unnamed

Percent of map unit: 7 percent

Hydric soil rating: No

WnA—Wilson clay loam, 0 to 2 percent slopes

Map Unit Setting

National map unit symbol: 2wg9b

Elevation: 380 to 870 feet

Mean annual precipitation: 37 to 42 inches

Mean annual air temperature: 64 to 67 degrees F

Frost-free period: 250 to 255 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Wilson and similar soils: 85 percent

Custom Soil Resource Report

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Wilson

Setting

Landform: Stream terraces

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Concave

Parent material: Loamy and/or clayey alluvium derived from mudstone

Typical profile

Ap - 0 to 7 inches: clay loam

Btss - 7 to 31 inches: clay

Btkss - 31 to 36 inches: clay

Btkssyg - 36 to 42 inches: clay

Btkyg - 42 to 80 inches: clay loam

Properties and qualities

Slope: 0 to 2 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Moderately well drained

Runoff class: High

Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 20 percent

Gypsum, maximum in profile: 15 percent

Salinity, maximum in profile: Very slightly saline to moderately saline (2.0 to 8.0 mmhos/cm)

Sodium adsorption ratio, maximum in profile: 10.0

Available water storage in profile: Moderate (about 7.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3w

Hydrologic Soil Group: D

Ecological site: Claypan Prairie 28-40" PZ (R086AY200TX)

Hydric soil rating: No

Minor Components

Burleson

Percent of map unit: 10 percent

Landform: Stream terraces, stream terraces

Landform position (three-dimensional): Tread

Microfeatures of landform position: Circular gilgai, circular gilgai

Down-slope shape: Linear

Across-slope shape: Linear

Ecological site: Blackland 28-40" PZ (R086AY196TX)

Hydric soil rating: No

Crockett

Percent of map unit: 5 percent

Custom Soil Resource Report

Landform: Ridges

Landform position (two-dimensional): Summit, shoulder

Landform position (three-dimensional): Interfluve

Down-slope shape: Linear

Across-slope shape: Convex

Ecological site: Claypan Prairie 28-40" PZ (R086AY200TX)

Hydric soil rating: No

McLennan County, Texas

CrB—Crockett loam, 3 to 5 percent slopes

Map Unit Setting

National map unit symbol: 2vv4y
Elevation: 380 to 610 feet
Mean annual precipitation: 35 to 37 inches
Mean annual air temperature: 65 to 67 degrees F
Frost-free period: 240 to 270 days
Farmland classification: Farmland of statewide importance

Map Unit Composition

Crockett and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Crockett

Setting

Landform: Ridges
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Down-slope shape: Linear
Across-slope shape: Convex
Parent material: Loamy residuum weathered from shale of cretaceous age

Typical profile

A - 0 to 8 inches: loam
Btss - 8 to 25 inches: clay
Btkss - 25 to 45 inches: clay
BCK - 45 to 53 inches: clay
Cdk - 53 to 72 inches: clay loam

Properties and qualities

Slope: 3 to 5 percent
Depth to restrictive feature: 43 to 60 inches to densic bedrock
Natural drainage class: Moderately well drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.03 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 30 percent
Gypsum, maximum in profile: 2 percent
Salinity, maximum in profile: Nonsaline to slightly saline (0.0 to 4.0 mmhos/cm)
Sodium adsorption ratio, maximum in profile: 10.0
Available water storage in profile: Moderate (about 8.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: D
Ecological site: Claypan Prairie 28-40" PZ (R086AY200TX)

Custom Soil Resource Report

Hydric soil rating: No

Minor Components

Heiden

Percent of map unit: 10 percent
Landform: Ridges
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Microfeatures of landform position: Linear gilgai
Down-slope shape: Linear
Across-slope shape: Convex
Ecological site: Blackland 28-40" PZ (R086AY196TX)
Hydric soil rating: No

Wilson

Percent of map unit: 5 percent
Landform: Stream terraces
Landform position (three-dimensional): Tread
Microfeatures of landform position: Open depressions
Down-slope shape: Linear
Across-slope shape: Concave
Ecological site: Claypan Prairie 28-40" PZ (R086AY200TX)
Hydric soil rating: No

HeC—Heiden clay, 3 to 5 percent slopes

Map Unit Setting

National map unit symbol: 2v1vc
Elevation: 260 to 890 feet
Mean annual precipitation: 33 to 42 inches
Mean annual air temperature: 63 to 68 degrees F
Frost-free period: 233 to 260 days
Farmland classification: All areas are prime farmland

Map Unit Composition

Heiden and similar soils: 85 percent
Minor components: 15 percent
Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Heiden

Setting

Landform: Ridges
Landform position (two-dimensional): Shoulder, backslope
Landform position (three-dimensional): Side slope, interfluve
Microfeatures of landform position: Linear gilgai
Down-slope shape: Convex
Across-slope shape: Convex
Parent material: Clayey residuum weathered from mudstone

Custom Soil Resource Report

Typical profile

Ap - 0 to 6 inches: clay
Bkss1 - 6 to 18 inches: clay
Bkss2 - 18 to 58 inches: clay
CBdk - 58 to 80 inches: clay

Properties and qualities

Slope: 3 to 5 percent
Depth to restrictive feature: 40 to 65 inches to densic material
Natural drainage class: Well drained
Runoff class: Very high
Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)
Depth to water table: More than 80 inches
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate, maximum in profile: 40 percent
Gypsum, maximum in profile: 5 percent
Salinity, maximum in profile: Nonsaline to very slightly saline (0.0 to 2.0 mmhos/cm)
Sodium adsorption ratio, maximum in profile: 12.0
Available water storage in profile: High (about 9.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified
Land capability classification (nonirrigated): 3e
Hydrologic Soil Group: D
Ecological site: Blackland 28-40" PZ (R086AY196TX)
Hydric soil rating: No

Minor Components

Houston black

Percent of map unit: 10 percent
Landform: Ridges
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Microfeatures of landform position: Circular gilgai
Down-slope shape: Convex
Across-slope shape: Linear
Ecological site: Blackland 28-40" PZ (R086AY196TX)
Hydric soil rating: No

Ferris, moderately eroded

Percent of map unit: 5 percent
Landform: Ridges
Landform position (two-dimensional): Backslope
Landform position (three-dimensional): Side slope
Microfeatures of landform position: Linear gilgai
Down-slope shape: Linear
Across-slope shape: Convex
Ecological site: Eroded Blackland 28-40" PZ (R086AY201TX)
Hydric soil rating: No

WnA—Wilson clay loam, 0 to 2 percent slopes

Map Unit Setting

National map unit symbol: 2wg9b

Elevation: 380 to 870 feet

Mean annual precipitation: 37 to 42 inches

Mean annual air temperature: 64 to 67 degrees F

Frost-free period: 250 to 255 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Wilson and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Wilson

Setting

Landform: Stream terraces

Landform position (three-dimensional): Tread

Down-slope shape: Linear

Across-slope shape: Concave

Parent material: Loamy and/or clayey alluvium derived from mudstone

Typical profile

Ap - 0 to 7 inches: clay loam

Btss - 7 to 31 inches: clay

Btkss - 31 to 36 inches: clay

Btkssyg - 36 to 42 inches: clay

Btkyg - 42 to 80 inches: clay loam

Properties and qualities

Slope: 0 to 2 percent

Depth to restrictive feature: More than 80 inches

Natural drainage class: Moderately well drained

Runoff class: High

Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum in profile: 20 percent

Gypsum, maximum in profile: 15 percent

Salinity, maximum in profile: Very slightly saline to moderately saline (2.0 to 8.0 mmhos/cm)

Sodium adsorption ratio, maximum in profile: 10.0

Available water storage in profile: Moderate (about 7.6 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Custom Soil Resource Report

Land capability classification (nonirrigated): 3w
Hydrologic Soil Group: D
Ecological site: Claypan Prairie 28-40" PZ (R086AY200TX)
Hydric soil rating: No

Minor Components

Burleson

Percent of map unit: 10 percent
Landform: Stream terraces, stream terraces
Landform position (three-dimensional): Tread
Microfeatures of landform position: Circular gilgai, circular gilgai
Down-slope shape: Linear
Across-slope shape: Linear
Ecological site: Blackland 28-40" PZ (R086AY196TX)
Hydric soil rating: No

Crockett

Percent of map unit: 5 percent
Landform: Ridges
Landform position (two-dimensional): Summit, shoulder
Landform position (three-dimensional): Interfluve
Down-slope shape: Linear
Across-slope shape: Convex
Ecological site: Claypan Prairie 28-40" PZ (R086AY200TX)
Hydric soil rating: No

References

- American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.
- American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.
- Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.
- Federal Register. July 13, 1994. Changes in hydric soils of the United States.
- Federal Register. September 18, 2002. Hydric soils of the United States.
- Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.
- National Research Council. 1995. Wetlands: Characteristics and boundaries.
- Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262
- Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577
- Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580
- Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.
- United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.
- United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374
- United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>

Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf